KOLAR DIVISION.

Notice is hereby given that the travellers' bungalow at Chikballapur has been thoroughly disinfected and is now fit for occupation.

B. B. GARUDACHARYA,
Executive Engineer.

HASSAN DIVISION.

Dated 13th November 1911.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 4th December 1911, for constructing a scouring sluice for, and a superpassage in the 9th mile of the south channel of Sree Ramadevar Dam. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1912.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving and extending the south channel of Sree Ramadevar Dam," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate quantities of work to be done in connection with improving and extending the south channel of Sree Ramadevar Dam.

Description of work	*Unit*	*Quantity or number.*
Scouring sluice—		
Dismantling the old masonry	C. ft.	1,934
Burnt stone (roughly dressed)	„	636
Cut stone work	„	191
Brick in surki mortar	„	3,894
Stone arch work	„	20
Concrete in surki mortar	„	50
Stone slab 1 foot thick	S. ft.	113
Do 9″ thick	„	65
Do 6″ thick	„	102
Do 4″ thick	„	365
Do 3″ thick	„	231
Teakwood wrought and put up	C. ft.	16
Pointing with cement	Sqr.	4·13
Plastering with surki mortar	„	8 82
Shutters for vents	No.	2
Holding down bolts with nuts and washers	„	3
Centerings for the arches	Lump sum	
Earthwork, excavation, foundation at the right end	Lump sum	
Superpassage in 9th mile—		
Earthwork, soft rock	Cyd.	464
Brick in surki mortar	C. ft.	14,618
Concrete in surki mortar	„	3,425
Burnt stone slabs 6″ thick	S. ft.	3,060
Do girders 9″ to 12″	C. ft.	1,033
Surki plastering	Sqr.	59·55
Rough stone in surki concrete	C. ft.	7,335
New rough stone work	Cyd.	1,147
Earthwork, training bank	„	4,914
Date stone	No.	1

A. PUTTUSWAMAIYA,
Assistant Engineer in charge of Hassan Division.